



N Grady Ave Ditch Rehabilitation

Locator map unavailable

PROJECT DETAILS

PROJECT ID	{FD3357E3-EC61-49A5-A988-FA2CED1BA3A0}
DEPARTMENT ID	SW250002
CONTRACT ID	
PROJECT TYPE	Stormwater Engineering
PROJECT STATUS	Closeout
PROJECT PHASE	P5: Closeout
NEIGHBORHOOD	
COUNCIL DISTRICT	6
COMMUNITY REDEVELOPMENT AREA (CRA)	Not in a CRA
FUNDING SOURCE	Stormwater Improvement Fee
FUNDING COMMENTS	No additional funding comments

ESTIMATED PROJECT COST
\$1300000.00

ESTIMATED SCHEDULE

CONSTRUCTION FISCAL YEAR	2025
PROJECTED START DATE	04/01/2025
PROJECTED END DATE	10/01/2025

CONTACT

Detail map unavailable

PROJECT PHASE



To learn more about what activities are completed during each project phase, visit tampa.gov/projects

PROJECT DESCRIPTION

The project is located on the east side of N Grady Avenue, just south of W Spruce Street, and is identified as part of the Grady Avenue Drainage Improvements. The work includes demolition of trees and guardrail, installation of ten (10) storm sewer structures and large diameter piping to enclose an existing 800-ft ditch corridor. Improvements include approximately 200 feet of 36-inch reinforced concrete pipe (RCP) and approximately 490 feet of 60x38-inch elliptical reinforced concrete pipe (ERCP), along with all related miscellaneous and appurtenant work needed to enhance conveyance and corridor safety.

COMMUNITY BENEFITS

Maintain Stormwater Flow Needs | Reduce Erosion Concerns | Improve Public Safety | Reduce Future Maintenance Needs

